BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of Work: UGD Maintanance in Sidedahalli Village limit in Ward No 14, Bagalagunte

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications	cum	154.35	299.98	Rupees Two hundred Ninty nine & Ninty eight Paise only
2	Providing and laying in position to required level or slope 300mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications	m	98.00	661.44	Rupees Six hundred sixty one & Forty four Paise only
3	Constructing brick masonry circular type manhole 0.91m internal dia at bottom 0.91 m deep and 0.56m dia at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3,finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsixe granite metal finished with a floating coat of	No.s	13.00	14391.62	Rupees Fourteen thousand Three hundred ninty one & Sixty two Paise only
4	Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	cum	6.48	7086.10	Rupees Seven thousand eighty six & ten paise only
5	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	sqm	50.70	248.04	Rupees Two hundred forty eight & four paise only
6	Providing & Fixing SFRC Cover and frame 560mm (ID) Heavy Duty.	each	66.00	954.00	Rupees Nine hundred Fifty four only

Executive Engineer

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDE, BBMP DIVISION
BENGALURU-560 010

	filling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of all labour complete as specifications. allow 60% of rate considered under item	cum	154.35	80.56	Rupees Eighty & fifty six paise only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer